



Sree Chaitanya Mahavidyalaya

Formerly Sree Chaitanya College of Commerce

P.O. : Habra-Prafullanagar, North 24 Parganas, Pin - 743268

Ref. No. Scm/ten-10/27/23

Date : 17/07/2023

NOTICE

Inviting Tenders for Details estimate cost of Repairing works of Boys Hostel .

Sealed tenders are invited from eligible Contractor/Service Provider for undertaking the Details estimate cost of Repairing works of Boys Hostel of Sree Chaitanya Mahavidyalaya , Habra-Prafullanagar, North 24 Parganas,


The detail of the work to be done is as follows:

SL.No.	Description of work	Qty	Unit	Rate	Amounts
1	Dismantling artificial stone flooring upto 50 mm. thick by carefully chiselling without damaging the base and removing rubbish as directed within a lead of 75 m.	23.25	Sq.M		
2	250 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	0.26	Cu.M		
3	Supplying, Fitting & Fixing Factory made prelaminated P.V.C. door frame of size 50 mmx47 mm with a wall thickness of 5 mm, made out of extruded 5 mm Prelaminated PVC sheet miter cut at two corners and joined with two nos of 1.5 mm long brackets of 15 mm x15 mm M.S. square tube. The two vertical door profiles are to be einforced with 19 mmx 19 mm M.S. Square tube of 19 gauge, weather seal to be provided through out the frame. The door frame shall be fixed with the wall using 65/100 mm M.S. Screws through the frame by using P.V.C fasteners. A minimum of 4 Nos of screws to be provided for each vertical member and minimum 2 Nos for horizontal member etc. complete as per Manufacturer"s specification and direction of Engineer-in-Charge.	9.50	Sq.M		
4	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor.P.No-125, It No.-14 (ii) 25 mm thick PvC Door sh. Pan.	2.70	Sq.M		
5	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).	18.50	Sq.M		
6	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame exluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be correted upto three decimals). P.No-114, It No.-1	0.350	Cu.M		
7	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (vii) 100mm. X 58mm. X 1.90mm. P.No-140, It No.-5	85	Each		

8	Iron socket bolt of approved quality fitted and fixed complete.	25	Each		
9	Anodised aluminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete:	8	Each		
10	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc.	1	Each		
11	Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239. PVC Pipes 40 mm	22.50	Mtr		
12	40 mm Elbow (90°),	12	Each		
13	40 mm PVC Socket,	9	Each		
14	40 mm PVC Cross Tee,	6	Each		
15	40 mm Pipe Clip	20	Each		
16	Solvent Cement (250 Gr),	5.00	Gr		
17	25 mm G.I. Plug,	10	Each		
18	25 mm PVC Elbu,	21	Each		
19	25 PVC Union,	8	Each		
20	25 mm Tee,	18	Each		
21	25 mm Socket,	12	Each		
22	25mmX15mm M/Elbow,	12	Each		
23	Long Bend (90 Degree),	6	Each		
24	Nipple (75 mm long),	16	Each		
25	Nipple (100 mm long),	8	Each		
26	Nipple (150 mm long),	2	Each		
27	Nipple (200 mm long),	8	Each		
28	Nipple (300 mm long),	12	Each		
29	(J) Threaded End Cap. 25 mm,	14	Each		
30	25 mm Pipe Clip,	49	Each		
31	Hand Shower(Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar)	6	Each		

Terms and Conditions for eligibility:

1. Application for tender must include attested copy of valid GSTIN, I.Tax, Trade License, PAN Card and credentials for work done.
2. No quoted price above the cost of work mentioned will be accepted.
3. No extra cost will be borne by the college.
4. Payment will be made in favour of the selected bidder in crossed cheque (A/C payee only) on successful completion of works and observation of necessary formalities as the authority deems fit from time to time.
5. The successful bidder has to start of work within 07 days from the date of issue of work order.
6. **Time-schedule is as follows:**
 - i) Opening date of submission of tender papers: **18.07.2023**
 - ii) Closing date of submission of sealed tender: **25.07.2023**
 - iii) Tentative date and time for opening tender: **26.07.2023**

 17.07.23
Principal

Copy forwarded to:

1. College Notice board/College Website
2. Ashoknagar-Kalyangarh Municipality
3. Ashoknagar Post-office
4. The Convener, Development & Maintenance Sub-Committee,
5. Head Clerk

Sree Chaitanya Mahavidyalaya

Principal

Sree Chaitanya Mahavidyalaya
Habra-Prafullangar, 24 Pgs. (N)