



Sree Chaitanya Mahavidyalaya

Formerly Sree Chaitanya College of Commerce

P.O. : Habra-Prafullanagar, North 24 Parganas, Pin - 743268

NOTICE

Ref. No.

Date :

Inviting Tenders for partition of Class Room Wall

Sealed tenders are invited from eligible Manufacturers/Suppliers for undertaking the under mentioned works.

SREE CHAITANYA MAHAVIDYALAYA

Formerly sree Chaitanya College of Commerce

P.O.:- Habra-Prafullanagar, North 24 Parganas, Pin- 743268

Details Estimate of Construction of old Class room partition wall works for additional class room of Sree Chaitanya Mahavidyalaya at Prafullanagar, Habra, North 24 Parganas. Under Ashokenagar Kalyangarh Municipality,

Sl No.	Description of Item	Quantity	Unit	Rate	Amounts Rs.
1	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. P.no -26, Sl no- 10(i)	0.32	m ³		
	Beam Linlet				
	2 nos x 8.50 mx 0.125 mx 0.150 m=	0.32			
2	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of 1st floor) P.no -42, Sl no- 36	2.55	m ²		
	Beam Linlet				
	2 nos x 8.50 mx 0.150 m=	2.55			
3	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction I Page -43, Sl no- 40	0.0031	MT		
	8.50 mx 4.0 m ³ 0.62 m=	0.21			
	5' 00 mx 0.45 m ³ 0.395 m=	0.10			
		0.31			
4	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in Ground floor. Page -16, Sl no- 16	29.75	m ²		
	Partition wall				
	1 nos x 8.500 mx 3.500 m=	29.75			
5	Plaster to ceiling with sand cement mortar (4:1) 10 mm thick P.No.-189, Sl no- 1/1 (b)	59.50	m ²		
	Partition wall				
	1 nos x 8.500 mx 3.500 m=	59.50			
6	Net Cement	5.10	m ²		
	Partition wall				
	2 nos x 8.500 mx 0.300 m=	5.10			
7	Applying interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per anufacturer's specification and as per direction of the EIC. (In Ground Floor) P.No.- 195, It. No.- 7 (b)	59.50	m ²		
8	Protectiveand Decorative Acrylic exterior emulsionpaint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) P.No.- 197, It. No.- 17	59.50	m ²		

30/11/22

Principal
Sree Chaitanya Mahavidya
Habra-Prafullanagar, 24 Pgs



Sree Chaitanya Mahavidyalaya

Formerly Sree Chaitanya College of Commerce

P.O. : Habra -Prafullanagar, North 24 Parganas, Pin - 743268

P.O. : Habra -Prafullanagar, North 24 Parganas, Pin - 743268

Ref. No. Estimate of Construction of Annex Building's Two Class room partition wall works for add **Date** class room of Sree Chaitanya Mahavidyalaya at Prafullanagar, Habra, North 24 Parganas. Under Ashokenagar Kalyangarh Municipality,

Sl No.	Description of Item	Quantity	Unit	Rate	Amounts Rs.
1	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. P.no -26, Sl no- 10(i)	0.27	m ³		
	Beam Linlet				
	2 no x 6.000 mx 0.15 mx 0.150 m=	0.27			
2	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of 1st floor) P.no -42, Sl no- 36	1.80	m ²		
	Beam Linlet				
	2 no x 6.00 mx 0.150 m=	1.80			
3	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction I Page -43, Sl no- 40	0.0044	MT		
	(a) For works in foundation, basement and upto roof of ground floor/upto 4 m				
	4 no x 12 mx 0.620 m=	0.30			
	82 no x 0.45 mx 0.395 m=	0.15			
		0.44			
4	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in Ground floor. P. no. -16, Sl no- 16	42.00	m ²		
	Partition wall				
	2 no x 6.000 mx 3.500 m=	42.00			
5	Plaster to ceiling with sand cement mortar (4:1) 10 mm thick P.No.-189, Sl no- 1/i (b)	84.00	m ²		
	Partition wall				
	2 no x 12.000 mx 3.500 m=	84.00			
6	Net Cement	7.20	m ²		
	Partition wall				
	2 no x 12.000 mx 0.300 m=	7.20			
7	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor) P.No.- 195, It. No.- 7 (b)	84.00	m ²		
8	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) P.No.- 197, It. No.- 17	84.00	m ²		

Terms and Conditions for eligibility:

1. Application for tender must include attested copy of valid GST IN, I.Tax, Trade License, PAN Card and credentials for work done.
2. No quoted price above the cost of work mentioned will be accepted.
3. No extra cost will be borne by the college.

(Signature)
30.11.22

Principal
Sree Chaitanya Mahavidyalaya
Habra-Prafullanagar, 24 Pgs. (I)



Sree Chaitanya Mahavidyalaya


Formerly Sree Chaitanya College of Commerce

P.O. : Habra-Prafullanagar, North 24 Parganas, Pin - 743268

Ref. No.

Date :

4. Payment will be made in favour of the selected bidder in crossed cheque (A/C payee only) on successful completion of works and observation of necessary formalities as the authority deems fit from time to time.
5. The successful bidder has to start of work within 07 days from the date of issue of work order.
6. **Time-schedule is as follows:**
 - i) Opening date of submission of tender papers: **30.11.2022**
 - ii) Closing date of submission of sealed tender: **08.12.2022**
 - iii) Tentative date and time for opening tender: **09.12.2022**

 30.11.22

Principal

Sree Chaitanya Mahavidyalaya

Copy forwarded to:

1. College Notice board/College Website
2. The Convener, Purchase Committee,
3. Head Clerk

Principal
Sree Chaitanya Mahavidyalaya
Habra-Prafullanagar, 24 Pgs. (N)